




METAL DOOR



L.H. DOOR


R.H. DOOR

- NOTES:
- DRAWING IS NOT TO SCALE.
 - PREPARATION DETAILS ARE IN SUPPLEMENT TO ANSI/BHMA A156.115 AND/OR A115W.
 - REFERENCE STRIKE TEMPLATE FOR DETAILS TO PREPARE FRAME.
 - FOR ELECTROLYNX APPLICATIONS, REFER TO MCKINNEY TRANSFER DEVICE CATALOG.
 - VERTICAL CENTERLINE IS REFERENCED FROM THE CENTERLINE OF THE BEVEL. (INDUSTRY STANDARD BEVEL IS 1/8 INCH IN 2 INCHES.)
 - CONSULT THE AUTHORITY HAVING JURISDICTION (AHJ) TO VERIFY THE RECOMMENDED MOUNTING HEIGHT ABOVE THE FINISHED FLOOR (AFF). LIMITATIONS IN THE DOOR CONSTRUCTION PROCESS MAY REQUIRE SOME HOLES TO BE FIELD-LOCATED USING THE PHYSICAL PART AS A TEMPLATE.
 - STANDARD TOLERANCE OF \pm .015 APPLIES TO ALL DOOR PREPARATION REQUIREMENTS, UNLESS OTHERWISE SPECIFIED.
 - DOOR REINFORCEMENT IS RECOMMENDED TO IMPROVE (SURFACE MOUNTED) FASTENER HOLDING POWER AND CRUSH RESISTANCE (WHEN THRU-BOLTING IS EMPLOYED). CONSTRUCTION TECHNIQUES SHOULD REFLECT INDUSTRY BEST PRACTICES (I.E. WDMA, SDI) AND AUTHORIZED METHODS WHERE LABEL SERVICE (I.E. UL, W-H) IS IN EFFECT.
 - WIRE RACEWAY AREAS SHOULD BE FREE OF OBSTRUCTIONS & SHARP EDGES TO PROTECT WIRES FROM CUTS & ABRASIONS.
 - CAREFULLY NOTE WHICH FEATURES ARE OPTIONAL, (WHETHER THE FEATURE APPLIES TO BOTH SIDES OF THE DOOR AND/OR IF A DEPTH APPLIES.)
 - MAXIMUM PRODUCT DIMENSIONS ARE SHOWN FOR THE PURPOSE OF VERIFYING FITMENT WITH DOOR FRAME STOPS, DOOR STILE SIZE & LIGHT/LOUVER KITS.
 - IF OPTIONAL LEVERS OR ROSES ARE USED REFERENCE THE RELATED PRODUCT DIMENSIONS TO VERIFY THE FITMENT REQUIREMENTS.



LOCK FUNCTION	TRIM OPTIONS TABLE							
	"A" O/S CYLINDER	"B" I/S CYLINDER	"C" I/S TURN	"D" O/S TURN	"E" O/S LEVER	"F" I/S LEVER	"G" I/S INDICATOR	"H" O/S INDICATOR
05, 24, 25, 28, 43, 45, 47, 50, 51, 56, 57, 58, 67, 281	X		X		X	X		
39, 37	X				X	X		
26, 29, 38, 39, 40, 41, 46, 52	X	X			X	X		
65, 66, 68			X	X	X	X		
12, 285			X		X	X		
21	X		X					
36	X				X			
20	X							
22	X	X						
INDICATOR OPTION (ADD HOLES)								
V* (INDICATOR OUTSIDE)			X	X				X
V* (INDICATOR INSIDE)							X	X
V** (INDICATOR BOTH SIDES)			X	X			X	X
* INDICATOR WINDOW OPTION CODE								

PREFIXES & FUNCTIONS	LOCK POCKET OPTIONS TABLE	
	DIM "J" LOCK FRONT	DIM "K" POCKET WIDTH
STANDARD	1.250 \pm .015	.906
1- PREFIX	1.062 \pm .015	.906
74- PREFIX	1.250 \pm .015	1.125
RX- PREFIX OR 281/285 FUNCTIONS	1.250 \pm .015	1.250
38 FUNCTION	1.250 \pm .015	1.125 \pm .062
		4.125





SARGENT ASSA BLOY Sargent Manufacturing Company
100 Sargent Drive New Haven, CT 06511

DOOR MANUFACTURERS TEMPLATE: RELEASE DATE
SECTIONAL INDICATOR TRIM APRIL 2019
METAL DOOR
8200 MORTISE LOCK
TEMPLATE NO. 4747 3

SHEET 1 OF 2


WOOD DOOR



L.H. DOOR


R.H. DOOR

- NOTES:**
- DRAWING IS NOT TO SCALE.
 - PREPARATION DETAILS ARE IN SUPPLEMENT TO ANSI/BHMA A156.115 AND/OR A115W.
 - REFERENCE STRIKE TEMPLATE FOR DETAILS TO PREPARE FRAME.
 - FOR ELECTROLYNX APPLICATIONS, REFER TO MCKINNEY TRANSFER DEVICE CATALOG.
 - VERTICAL CENTERLINE IS REFERENCED FROM THE CENTERLINE OF THE BEVEL. (INDUSTRY STANDARD BEVEL IS 1/8 INCH IN 2 INCHES.)
 - CONSULT THE AUTHORITY HAVING JURISDICTION (AHJ) TO VERIFY THE RECOMMENDED MOUNTING HEIGHT ABOVE THE FINISHED FLOOR (AFF).
 - LIMITATIONS IN THE DOOR CONSTRUCTION PROCESS MAY REQUIRE SOME HOLES TO BE FIELD-LOCATED USING THE PHYSICAL PART AS A TEMPLATE.
 - STANDARD TOLERANCE OF $\pm .015$ APPLIES TO ALL DOOR PREPARATION REQUIREMENTS, UNLESS OTHERWISE SPECIFIED.
 - DOOR REINFORCEMENT IS RECOMMENDED TO IMPROVE (SURFACE MOUNTED) FASTENER HOLDING POWER AND CRUSH RESISTANCE (WHEN THRU-BOLTING IS EMPLOYED). CONSTRUCTION TECHNIQUES SHOULD REFLECT INDUSTRY BEST PRACTICES (I.E. WDMA, SDI) AND AUTHORIZED METHODS WHERE LABEL SERVICE (I.E. UL, W-H) IS IN EFFECT.
 - WIRE RACEWAY AREAS SHOULD BE FREE OF OBSTRUCTIONS & SHARP EDGES TO PROTECT WIRES FROM CUTS & ABRASIONS.
 - CAREFULLY NOTE WHICH FEATURES ARE OPTIONAL, (WHETHER THE FEATURE APPLIES TO BOTH SIDES OF THE DOOR AND/OR IF A DEPTH APPLIES.)
 - MAXIMUM PRODUCT DIMENSIONS ARE SHOWN FOR THE PURPOSE OF VERIFYING FITMENT WITH DOOR FRAME STOPS, DOOR STILE SIZE & LIGHT/LOUVER KITS.
 - IF OPTIONAL LEVERS OR ROSES ARE USED REFERENCE THE RELATED PRODUCT DIMENSIONS TO VERIFY THE FITMENT REQUIREMENTS.



LOCK FUNCTION	TRIM OPTIONS TABLE							
	"A" O/S CYLINDER	"B" I/S CYLINDER	"C" I/S TURN	"D" O/S TURN	"E" O/S LEVER	"F" I/S LEVER	"G" I/S INDICATOR	"H" O/S INDICATOR
05, 24, 25, 28, 43, 45, 47, 50, 51, 56, 57, 58, 67, 281	X		X		X	X		
30, 37	X				X	X		
26, 29, 38, 39, 40, 41, 46, 52	X	X			X	X		
45, 46, 48			X	X	X	X		
12, 285			X		X	X		
21	X		X					
36	X				X			
20	X							
22	X	X						
INDICATOR OPTION (ADD HOLES)								
V* O (INDICATOR OUTSIDE)				X				X
VO* (INDICATOR INSIDE)				X			X	
V** (INDICATOR BOTH SIDES)				X	X			X
* INDICATOR WINDOW OPTION CODE								

PREFIXES & FUNCTIONS	LOCK POCKET OPTIONS TABLE		
	DIM "J" LOCK FRONT	DIM "K" POCKET WIDTH	DIM "L" POCKET DEPTH
STANDARD	1.250 ± 0.15	.906	4.125
1- PREFIX	1.062 ± 0.15	.906	4.125
74- PREFIX	1.250 ± 0.15	1.125	4.250
RX- PREFIX OR 281/285 FUNCTIONS	1.250 ± 0.15	1.250	4.375
36 FUNCTION	1.250 ± 0.15	1.125 ± 0/-062	4.125



SARGENT Sargent Manufacturing Company
100 Sargent Drive New Haven, CT 06511

ASSA ABLOY

DOOR MANUFACTURERS TEMPLATE: RELEASE DATE
SECTIONAL INDICATOR TRIM APRIL 2019
WOOD DOOR
8200 MORTISE LOCK TEMPLATE NO.
4747 3

SHEET 2 OF 2